MYSORE DIVISION.

Dated 13th October 1906.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 30th October 1906, for restoring the Koratagere tank, Registered No. 413, Krishnarajpete Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1907.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Koratagere Tank, Krishnarajpete Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work.	*Per*	*Quantity.*
Bund.		
Earthwork including consolidation and breach filling ...	C. yds.	13,468
Turfing	Sqr.	1,196·03
Grade stones with bed slabs	Each.	28
Bench mark stone	"	2
Registered number stone	"	1
Gauge number stone	"	1
Date stone	"	1
New stone work	C. yd.	565
Gravel backing	"	96
Clearing jungle, stepping the bund and breach, etc. ...	Lump sum.	
Sluices.		
Right and left sluices—		
Brick in surki mortar	C. ft.	849
Burnt stone slabs dressed	S. ft.	296
Plastering with surki mortar	Sqr.	3·70
Plug with rod, etc.	Lump sum.	
Shifting and repairing old upright stone with top slabs ...	Do	
Excavating foundation and refilling	Do	
Left Waste Weir, 370 feet long.		
Earthwork, excavation and extending weir, etc. ...	Lump sum.	
Burnt brick in surki mortar	C. ft.	4,111
Burnt stone slabs dressed	S. ft.	1,137
Plastering with surki mortar	Sqr.	25·50
Rough stone work	C. yd.	754
Old stone work	"	169
Distribution.		
Improving the existing channel and putting embankment across the old right codi channel for taking the right sluice channel beyond, etc.	Lump sum.	
Miscellaneous.		
Compensation for submerging land at the bed of the tank as per previous amount.	Do	

P. SUBBA RAO,
Executive Engineer.